

ROUTE	STATE	DISTRICT	SHEET NO.
	MO		
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
COUNTY			DATE

"THIS MEDIA SHOULD NOT BE CONSIDERED A CERTIFIED DOCUMENT."

SIGN	SIZE (IN.)	AREA (SQ. FT.)	QTY	TOTAL AREA	QTY RELOC	TOTAL RELOC AREA	DESCRIPTION	SIGN	SIZE (IN.)	AREA (SQ. FT.)	QTY	TOTAL AREA	QTY RELOC	TOTAL RELOC AREA	DESCRIPTION
WARNING SIGNS								GUIDE SIGNS							
WD1-1L	48X48	16.00					TURN (SYMBOL LEFT ARROW)	SPECIAL	36X36	9.00					FRESH OIL/LOOSE GRAVEL
WD1-1R	48X48	16.00					TURN (SYMBOL RIGHT ARROW)	E05-1	36X48	12.00					GORE EXIT
WD1-2L	48X48	16.00					CURVE (SYMBOL LEFT ARROW)	E05-2	48X36	12.00					EXIT OPEN
WD1-2R	48X48	16.00					CURVE (SYMBOL RIGHT ARROW)	E05-2a	48X36	12.00					EXIT CLOSED
WD1-3L	48X48	16.00					REVERSE TURN (SYMBOL LEFT ARROW)	G020-1	60X24	10.00					ROAD WORK NEXT XX MILES
WD1-3R	48X48	16.00					REVERSE TURN (SYMBOL RIGHT ARROW)	G020-2	48X24	8.00					END ROAD WORK
WD1-4L	48X48	16.00					REVERSE CURVE (SYMBOL LEFT ARROW)	G020-4	36X18	4.50					PILOT CAR FOLLOW ME
WD1-4R	48X48	16.00					REVERSE CURVE (SYMBOL RIGHT ARROW)	SPECIAL	42X30	8.75					PLEASE WAIT FOR PILOT CAR
WD1-4bL	48X48	16.00					DOUBLE ARROW REVERSE CURVE (SYMBOL LEFT ARROWS)	G023-1	36X12	3.00					WORK ZONE (PLAQUE)
WD1-4bR	48X48	16.00					DOUBLE ARROW REVERSE CURVE (SYMBOL RIGHT ARROWS)	M04-8a	24X18	3.00					END DETOUR
WD1-4cL	48X48	16.00					TRIPLE ARROW REVERSE CURVE (SYMBOL LEFT ARROWS)	M04-9L	48X36	12.00					DETOUR (LEFT ARROW)
WD1-4cR	48X48	16.00					TRIPLE ARROW REVERSE CURVE (SYMBOL RIGHT ARROWS)	M04-9R	48X36	12.00					DETOUR (RIGHT ARROW)
WD1-6	48X24	8.00					HORIZONTAL ARROW (SYMBOL)	M04-10L	48X18	6.00					DETOUR (ARROW LEFT)
WD1-6a	72X36	18.00					HORIZONTAL ARROW (SYMBOL ON BARRICADE)	M04-10R	48X18	6.00					DETOUR (ARROW RIGHT)
WD1-7	48X24	8.00					DOUBLE HEAD HORIZONTAL ARROW (SYMBOL)	M5-1L	21X15	2.19					ADVANCE LEFT TURN ARROW
WD1-7a	72X36	18.00					DOUBLE HEAD HORIZONTAL ARROW (SYMBOL ON BARRICADE)								
WD1-8	18X24	3.00					CHEVRON (SYMBOL)								
WD1-8a	36X48	12.00					CHEVRON (SYMBOL FOR DIVIDED HIGHWAYS)								
WD3-1a	48X48	16.00					STOP AHEAD (SYMBOL)								
WD3-2a	48X48	16.00					YIELD AHEAD (SYMBOL)								
WD3-3	48X48	16.00					SIGNAL AHEAD (SYMBOL)								
WD3-4	48X48	16.00					BE PREPARED TO STOP								
WD3-5	48X48	16.00					SPEED LIMIT XX AHEAD								
WD4-1L	48X48	16.00					MERGE (SYMBOL FROM LEFT)	R1-1	48X48	13.25					STOP
WD4-1R	48X48	16.00					MERGE (SYMBOL FROM RIGHT)	R1-2	48 TRI.	6.93					YIELD
WD5-1	48X48	16.00					ROAD/BRIDGE/RAMP NARROWS	R1-2a	36X36	9.00					TO ONCOMING TRAFFIC (PLAQUE)
WD5-3	48X48	16.00					ONE LANE BRIDGE	R1-3	20X9	1.25					X-WAY (PLAQUE)
WD5-5	48X48	16.00					NARROW LANES	R2-1	36X48	12.00					SPEED LIMIT XX
WD6-1	48X48	16.00					DIVIDED HIGHWAY (SYMBOL)								
WD6-2	48X48	16.00					DIVIDED HIGHWAY END (SYMBOL)	R3-1	48X48	16.00					NO RIGHT TURN (SYMBOL)
WD6-3	48X48	16.00					TWO WAY TRAFFIC (SYMBOL)	R3-2	48X48	16.00					NO LEFT TURN (SYMBOL)
WD7-3a	30X24	5.00					NEXT XX MILES (PLAQUE)	R3-3	36X36	9.00					NO TURNS
WD8-1	48X48	16.00					BUMP	R3-4	48X48	16.00					NO U-TURN (SYMBOL)
WD8-2	48X48	16.00					DIP	R3-7L	30X30	6.25					LEFT LANE MUST TURN LEFT
WD8-3	48X48	16.00					PAVEMENT ENDS	R3-7R	30X30	6.25					RIGHT LANE MUST TURN RIGHT
WD8-4	48X48	16.00					SOFT SHOULDER	R4-1	36X48	12.00					DO NOT PASS
WD8-5	48X48	16.00					SLIPPERY WHEN WET (SYMBOL)	R4-2	36X48	12.00					PASS WITH CARE
WD8-6	48X48	16.00					TRUCK CROSSING	R4-7aL	36X48	12.00					KEEP LEFT (HORIZONTAL ARROW)
WD8-6c	48X48	16.00					TRUCK ENTRANCE	R4-7a	36X48	12.00					KEEP RIGHT (HORIZONTAL ARROW)
WD8-7	36X36	9.00					LOOSE GRAVEL	R5-1	30X30	6.25					DO NOT ENTER
WD8-9	48X48	16.00					LOW SHOULDER	R5-1a	36X24	6.00					WRONG WAY
WD8-9a	48X48	16.00					SHOULDER DROP-OFF	R6-1L	48X18	6.00					ONE WAY ARROW (LEFT)
WD8-11	48X48	16.00					UNEVEN LANES	R6-1R	48X18	6.00					ONE WAY ARROW (RIGHT)
WD8-12	36X36	9.00					NO CENTER STRIPE	R6-2L	24X30	5.00					ONE WAY (LEFT)
W10-1	42 RND.	9.62					RAILROAD CROSSING	R6-2R	24X30	5.00					ONE WAY (RIGHT)
WD12-1	24X24	4.00					DOUBLE DOWN ARROW (SYMBOL)	R10-6	24X36	6.00					STOP HERE ON RED (45° ARROW)
WD12-2	48X48	16.00					LOW CLEARANCE (SYMBOL)	R11-2	48X30	10.00					ROAD CLOSED
WD12-2x	24X18	3.00					LOW CLEARANCE (PLAQUE)	R11-3a	60X30	12.50					ROAD CLOSED XX MILES AHEAD LOCAL TRAFFIC ONLY
WD12-3a,b	144X24	24.00					OVERHEAD LOW CLEARANCE (FEET AND INCHES)	R11-4	60X30	12.50					ROAD CLOSED TO THRU TRAFFIC
SPECIAL	120X60	50.00					LOW CLEARANCE XX FT XX IN XX MILES AHEAD	S4-4	36X15	3.75					WHEN FLASHING
SPECIAL	120X60	50.00					WIDTH RESTRICTION XX FT XX IN XX MILES AHEAD	CONST-3A	60X48	20.00					FINE SIGN
WD13-1	30X30	6.25					ADVISORY SPEED (PLAQUE)	CONST-3X	56X12	4.67					SPEEDING/PASSING (PLATE)
WD16-2	30X24	5.00					XXX FEET (PLAQUE)								
WD16-3	30X24	5.00					X MILE (PLAQUE)								
WD20-1	48X48	16.00					ROAD/BRIDGE/RAMP WORK AHEAD								
WD20-2	48X48	16.00					DETOUR AHEAD								
WD20-3	48X48	16.00					ROAD CLOSED AHEAD								
WD20-4	48X48	16.00					ONE LANE ROAD AHEAD								
WD20-5	48X48	16.00					RIGHT/CENTER/LEFT LANE CLOSED AHEAD	616-10.05							
WD20-5a	48X48	16.00					RIGHT/CENTER/LEFT TWO LANES CLOSED AHEAD	CONSTRUCTION SIGNS TOTAL							
WD20-6a	48X48	16.00					RIGHT/CENTER/LEFT LANE CLOSED	616-10.10							
WD20-7a	48X48	16.00					FLAGGER (SYMBOL)	RELOCATED SIGNS TOTAL							
WD21-2	36X36	9.00					FRESH OIL								
WD21-5b	48X48	16.00					SHOULDER WORK AHEAD								
WD22-1	48X48	16.00					BLASTING ZONE AHEAD								
WD22-2	42X36	10.50					TURN OFF 2-WAY RADIO AND PHONE								
WD22-3	42X36	10.50					END BLASTING ZONE								
WD22-6e	21X15	2.19					WET PAINT (ARROW PIVOTS)								

ITEM NUMBER	TOTAL QTY	DESCRIPTION
612-20.08		IMPACT ATTENUATOR (8 SAND BARRELS)
612-20.09		IMPACT ATTENUATOR (9 SAND BARRELS)
612-20.10		IMPACT ATTENUATOR (10 SAND BARRELS)
612-20.12		IMPACT ATTENUATOR (12 SAND BARRELS)
612-20.14		IMPACT ATTENUATOR (14 SAND BARRELS)
612-20.17		IMPACT ATTENUATOR (17 SAND BARRELS)
612-20.19		IMPACT ATTENUATOR (19 SAND BARRELS)
612-20.20		REPLACEMENT SAND BARREL
612-20.30		IMPACT ATTENUATOR ARRAY (RELOCATION)
612-30.00		TRUCK MOUNTED ATTENUATOR (TMA)
616-10.20		CHANNELIZER (DRUM-LIKE)
616-10.22		CHANNELIZER (CONES)
616-10.24		CHANNELIZER (TRIM LINE) WITH LIGHT
616-10.25		CHANNELIZER (TRIM LINE)
616-10.26		CHANNELIZER (VERTICAL PANEL)
616-10.27		CHANNELIZER (VERTICAL PANEL) WITH LIGHT
616-10.28		CHANNELIZER
616-10.29		TYPE III MOVEABLE BARRICADE WITH SIGN
616-10.30		TYPE III MOVEABLE BARRICADE
616-10.31		TYPE III MOVEABLE BARRICADE WITH LIGHT
616-10.32		TYPE III MOVEABLE BARRICADE WITH SIGN AND LIGHT
616-10.33		DIRECTION INDICATOR BARRICADE
616-10.34		DIRECTION INDICATOR BARRICADE, WITH LIGHT
616-10.40		FLASHING ARROW PANEL
616-10.47		TYPE III OBJECT MARKER
616-10.51		WARNING LIGHT, TYPE A
616-10.52		WARNING LIGHT, TYPE B
616-10.53		WARNING LIGHT, TYPE C
616-10.54		STROBE LIGHT
616-10.70		TUBULAR MARKER
616-10.95		RADAR SPEED ADVISORY SYSTEM
616-10.96		CHANGEABLE MESSAGE SIGN, COMMISSION FURNISHED/RETAINED
616-10.98		CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED/RETAINED
616-11.00		CHANGEABLE MESSAGE SIGN, CONTRACTOR FURNISHED/COMMISSION RETAINED
616-11.20		INSTALLING "DRIVE SMART", 48 IN. X 48 IN. SIGN
616-11.33		INSTALLING "POINT OF PRESENCE" SIGN
616-12.00		LAW ENFORCEMENT SERVICES
617-36.00C		CONTRACTOR FURNISHED/RETAINED TEMPORARY CONCRETE TRAFFIC BARRIER, TYPE F
617-36.02A		CONTRACTOR FURNISHED/COMMISSION RETAINED TEMPORARY CONCRETE TRAFFIC BARRIER, TYPE F
617-40.00		TEMPORARY CONCRETE BARRIER HEIGHT TRANSITION
617-50.10		RELOCATING TEMPORARY CONCRETE TRAFFIC BARRIER
617-60.00		COMMISSION FURNISHED/RETAINED TEMPORARY CONCRETE TRAFFIC BARRIER, TYPE F
617-70.00		COMMISSION FURNISHED/RETAINED PRECAST BARRIER HEIGHT TRANSITION
620-80.65		TEMPORARY RAISED PAVEMENT MARKER
901-94.00		TEMPORARY LIGHTING
902-94.00		TEMPORARY TRAFFIC SIGNALS
902-94.01		TEMPORARY TRAFFIC SIGNALS AND LIGHTING

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.